BRUHAT BANGALORE MAHANAGARA PALIKE, YELAHANKA ZONE

Executive Engineeer
Byatarayanapura Division
B.B.M.P., Bangalore - 92.

MODIFIED SCHEDULE - B

Name of Work: Development Works for Providing Drinking Water Facility in Ward No. 07 (Byatarayanapura), Kodigehalli Sub Division.

Sl. No.	Approved Quantity	Description	Unit	KRIDL Rates	
				In Figures	In Words
1	2	Geophysical investigation of site for sinking Borewell for supplying drinking water to the habitation either through the Hand pump, MWS of P.W.S.S by vertical electrical sounding by adopting Venner or Schlumberger's method, including reconnaissance survey of geological formation, Gerophysical investigation of existing Ground Wate in the vicinity, its quality & acceptability of the users indicating the location of site, recommended depth of casing pipe required to seal the top unconsolidated formation including an extra depth of 1.0 meter in consolidated formation for proper seating of casing pipe, depth of drilling required to cover full depth of aquifer proposed to be tapped, probable yield and other information required including transportation of instrument and accessories to work site., engaging techinical personal and labour required etc., as per Specification and direction ,with all lead and lift, loading, unloading and labour charges etc., complete and as per the directions of the Engineer-in-charge of the work	Each BW	1882.00	Rupees One Thousand Eight Hundred Eighty Two Only
2	100.00	Sinking borewell of 165 mm dia clear using super fast hydraulic rig of capacity 250 PSIG & above CFM & above in all strats including over burden upto 20 mts fixing of casing pipes, collars and cap with necessary cutting, throading and welding including transportation of rig and supporing vehicles, crew charges and cost of consumables etc., complete including yield testing at the final depth with a minimum working of compressor for one hour (excluding coat of casing pipes, collars and cap etc.,) ,with all lead and lift, loading, unloading and labour charges etc., complete and as per the directions of the Engineer-in-charge of the work 0 to 50 m	Rmtr	315.18	Rupees Three Hundred Fifteen And Paise Eighteen Only
	100.00	50 to 100 m	Rmtr	412.00	Rupees Four Hundred Twelve Only
	100.00	100 to 150 m	Rmtr	458.35	Rupees Four Hundred Fifty Eight And Paise Thirty Five Only
	100.00	150 to 200 m	Rmtr	484.10	Rupees Four Hundred Eighty Four And Paise Ten Only
	100.00	200 to 250 m	Rmtr	560.32	Rupees Five Hundred Sixty And Paise Thirty Two Only
	100.00	250 to 300 m	Rmtr	600.49	Rupees Six Hundred And Paise Forty Nine Only

Signature of the contractor

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010

20/09
Executive Engineer

20/09

	pproved Quantity	Description	Unit	KRIDL Rates In Figures	KRIDL Rates In Words
3	125.00	Supply of ISI mark 175 mm nominal bore medium black ERW casing pipe of 5 mm thick black electric resistance continuous welded mild steel tube material confirming to IS 1387 / 1993 & manufactured from hot rolled steel skelp / stripes in random length of 4 to 7 mts both ends threaded confirming to IS 554 / 1985, one end fixed with a socket and the other and with a plastic protection end (including of all taxes) ,with all lead and lift, loading, unloading and labour charges etc., complete and as per the directions of the Engineer-in-charge of the work	Rmtr	1325.00	Rupees One Thousand Three Hundred Twenty Five Only
				1325.00	#NAME?
	15.00	Qty above 125%			
4	36.00	Providing 250mm dia PVC Pipe 6kg/cm as per specification and direction of the Engineer in Charge of the work	Rmtr	1100.00	Rupees One Thousand One Hundred Only
5	2	Providing and fixing 160mm Borewell Cap ,with all lead and lift, loading, unloading and labour charges etc., complete and as per the directions of the Engineer-in-charge of the work	No.	100.00	Rupees One Hundred Only
6	1	Supply and delivery at site brand New texmo/ innoval/ Lubi/ Sabar / Atalanta/ Calamal/ make suitable for vertical installation in 150mm dia bore well comprising of single stage or multistage CF pump close coupled by measns of stainless steel coupling to suitable HP suitable speed totally enclosed and filled with pure drinking water (Wet type) squirrel cage submersible induction motor suitable for opertation of 3PH., 50 Hz, 380/440 volts AC supply fitted with required aqccessories such as suction, casing suction strainers sand guard Non return value etc. complete . The pump and motor shall form an integral unit with all the required fittings 10.00 HP 20 stage.with all lead and lift, loading, unloading and labour charges etc., complete and as per the directions of the Engineer-in-charge of the work 12.50 HP 20 stage	No	74300.00	#NAME?
7	290.00	Providing GI pipes confirming to IS specification of approved make with fittings such as collars bends elbows tees nipples plugs with cuts threads using white lead and threads for joints wherever necessary as per specifications including all lead and lift etc 50 mm dia GI Pipe B Class etc., complete and as per the directions of the Engineer-in-charge of the work	Rmtr	321.00	Rupees Three Hundred Twenty One Only
8	49.00	Heavy Duty Collar 50mm dia	Nos	130.00	Rupees One Hundred Thirty Only
9	590.00	Supplying and drawing 3 core flat PVC sheathed submersible pump cable manufactured with electrolytic grade copper with flexible copper conductor confirming to table 3 class 5 of IS:8130-1984 and virgin grade PVC insulation and sheathed suitable for working voltage upto 1100 Volts. with all lead and lift, loading, unloading and labour charges etc., complete and as per the directions of the Engineer-in-charge of the work	Mtr	126.70	Rupees One Hundred Twenty Six And Paise Seventy Only
10	49	Labour charges for erection as new /repaired submercible pumpset allong with GI pipe (32/50mm) cable (new submercible pumpset if required will be supplied by the department free of cost and released pumpset shoud be handed over to department including transportation (Each lenth =6.00) etc., complete and as per the directions of the Engineer-in-charge of the work	Length	88.00	Rupees Eighty Eight Only

Executive Engine

Signature of the contractor

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 016

	Approved Quantity	Description	Unit	KRIDL Rates	
				In Figures	In Words
	1	Supplying and fixing 20"x20"x2.5" polished wood board made of not less than 15mm thick plank on both sides with planks made out of not more than 2 pieces and fixing the same to the wall using tapered inverted wooden plugs screws etc., with all lead and lift, loading, unloading and labour charges etc., complete and as per the directions of the Engineer-in-charge of the work	No.	302.00	Rupees Three Hundred Two Only
12	30.00	Supplying of LTUG cable having aluminium condutor PVC insulated shethed, galvnised steel, wire / steel tap armoured cable with PVC outer sheathing 1.1 KV class.with all lead and lift, loading, unloading and labour charges etc., complete and as per the directions of the Engineer-in-charge of the work	Mtr	140.40	Rupees One Hundred Forty And Paise Forty Only
13	30.00	Labour charges for laying of 1.1 K.V class UG cable (PWD Electrical SR-1999-2000, with all lead and lift, loading, unloading and labour charges etc., complete and as per the directions of the Engineer-in-charge of the work	Mtr	10.80	Rupees Ten And Paise Eighty Only
14	25.00	Digging or trenching of 0.6 m x 0.5 m wide refilling the trench to the required ground level and consolidating etc., complete as per Civil SR KSRB 1-2 P-7 with all lead and lift, loading, unloading and labour charges etc., complete and as per the directions of the Engineer-in-charge of the work	Mtr	85.00	Rupees Eighty Five Only
15	4.00	Supplying and fixing of Class A (meaium duty) GI pipe of wall thickness not less than 3.25mm on pole/wall/drain crossing with necessary clamping arrangements for UG cable of 1.1 KV class with all lead and lift, loading,	Mtr	345.00	Rupees Three Hundred Forty Five Only
16	1	Supplying and fixing L.T. cast Iron pot head suitable for 1.1 KV class UG cable filled with necessary bituumen/insulating compound complete with terminals, clamps, bolts, nuts and washers etc.,with all lead and lift, loading, unloading and labour charges etc., complete and as per the directions of the Engineer-in-charge of the work	No.	280.00	Rupees Two Hundred Eighty Only
17	1	Supplying, fixing, wiring, earth electrode for grounding conduits, I.C cutouts and other equipments on the meter board using 40 mm dia 2.90 mm thick GI pipe 2.5 m long buried in a pit. The pit should be filled with equal propotion of solt and charocoal 150 mm alround the pipe to complete depth. The connection from the pipe to the conduit etc., is	No	2727.00	Rupees Two Thousand Seven Hundred Twenty Seven Only
18	6	Supplying and fixing of Porcelain fuse channel with cut out on existing wooden / panel using necessary nuts, bolts and washer etc.,with all lead and lift, loading, unloading and labour charges etc., complete and as per the directions of the Engineer-in-charge of the work	No.	180.00	Rupees One Hundred Eighty Only
19	1	Providing and fixing in position **50mm** nominal bore gun metal non-return valve horizontal type of approved make including cost of all materials, labour and HOM of equipments with all leads complete as per specifications. with all lead and lift, loading, unloading and labour charges etc., complete and as per the directions of the Engineer-in-charge of the work	No	1579.40	Rupees One Thousand Five Hundred Seventy Nine And Paise Forty Only

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010

Signature of the contractor

Executive Engineer

	Approved Quantity	Description	Unit	KRIDL Rates	
				In Figures	In Words
	1	Providing NP/CP waste unions conforming to ISI specifications and fixing them in position as per directions including cost of materials, fixtures and conveyance to work spot etc., complete.with all lead and lift, loading, unloading and labour charges etc., complete and as per the directions of the Engineer-in-charge of the work	No	227.90	Rupees Two Hundred Twenty Seven And Paise Ninety Only
21	4	SSupplying and fixing 50mm dia GI X nipple with ISI mark with all lead and lift loading unloading and labour etc., complete and as per the directions of the Engineer-in-charge of the work	No	104.30	Rupees One Hundred Four And Paise Thirty Only
22	1	Supplying shunt capaitors conforming to IS 2834, 3phase 400/440 volts grade for power factor improvement of rotating machinery, Capacitor in KVAR rating Nos. 2KVAR capacity with all lead and lift, loading, unloading and labour charges etc., complete and as per the directions of the Engineer-in-charge of the work	No	1350.00	Rupees One Thousand Three Hundred Fifty Only
23	1	Supplying and fixing miniature circuit breakers/solaters on existing MCB distribution boards using necessary fixing materiasl wiring complete as requireds 5 to 30 amps triple pole with all lead and lift, loading, unloading and labour charges etc., complete and as per the directions of the Engineer-in-charge of the work	No	1547.00	Rupees One Thousand Five Hundred Forty Seven Only
24	23400.00	Fabrication supplying and mounting MS box of 16 SWG suitable for floor /wall mounting, fully weather proof with provision for better heat dissipation, provided with hinged front cover, equipped with tamper proof locking arrangements, with suitable size clamps with necessary cable entry pipe with gland and box should be finished 2 coats of red oxide primer paint and finally finished with approved colour enamelled metal paint etc., complete box of 21600 sqcm with all lead and lift, loading, unloading and labour charges etc., complete and as per the directions of the Engineer-in-charge of the work	Sq.Cm	0.33	Rupees And Paise Thirty Three Only
25	1	Supplying fully automatic store detta starter unit push button type with suitable wires three contractors one adjustable termal timer mounted on a common base plate held in steel enclosure for use on 400/440 volts 3pase and wired offter fixing to the wooden board for motor upto 12.50 HP with all lead and lift, loading, unloading and labour charges etc., complete and as per the directions of the Engineer-in-charge of the work	No.	6583.00	Rupees Six Thousand Five Hundred Eighty Three Only
26	281.25	Earthwork excavation for pipeline foundation including deporiting or bank up to a depth of 50 mtrs including shiriry and statting danger lighting and using site rails and boming poles at every 100 mtrs wherever necessary as directed in th following strructure manhole with all lead and lift, loading, unloading and labour charges etc., complete and as per the directions of the Engineer-in-charge of the work	Cum	188.00	Rupees One Hundred Eighty Eight Only
	204.75			188.00	#NAME?

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 016

Signature of the contractor

20/9
Executive Engineer

20/09

	pproved Quantity	Description	Unit	KRIDL Rates In Figures	KRIDL Rates In Words
7	625.00	Providing and instalation at site of works P.V.C.Pipes including cost of pipes and specials and incluidng lowring into trenches, laying true to line, level and perfect linking at joints, leak proof including jointing encasing the pipe alround to a depth Not less than 15cm with grave or selected earth avalabile from the execavation with all lead and lift, loading, unloading and labour charges etc., complete and as per the directions of the Engineer-in-charge of the work 75mm Dia 6 KSC	Rmtr	157.00	Rupees One Hundred Fifty Seven Only
	455.00	Qty above 125%		157.00	#NAME?
28	281.25	Refilling the bumont and pipeline treanches with secleted available earthe for trench excavation including authority condition in layers from thedi including disponsary of the sunplus earth with a heavy 200 mtrswith all lead and lift, loading, unloading and labour charges etc., complete and as per the directions of the Engineer-in-charge of the work	Cum	61.00	Rupees Sixty One Only
	204.75	Qty above 125%		61.00	
29	4	Providing and fixing in position brass gate valve with C.I wheel of approved quality (screwed end) 50mm nominal bore including cost of all materials, labour and HOM of equipments with all leads complete as per specification with all lead and lift, loading, unloading and labour charges etc., complete and as per the directions of the Engineer-in-charge of the work	Each	2120.00	Rupees Two Thousand One Hundred Twenty Only
		Borewell Repair Works			
31	27	Starter (with one year Guarantee) etc., complete and as per the directions of the Engineer-in-charge of the work	No.	5050.00	Rupees Five Thousand Fifty Only
32	27	Rotor (with one year Guarantee) etc., complete and as per the directions of the Engineer-in-charge of the work	No.	4700.00	Rupees Four Thousand Seven Hundred Only
33	27	Upper Flange etc., complete and as per the directions of the Engineer-in-charge of the work	No.	350.00	Rupees Three Hundred Fifty Only
34	27	Lower Housing etc., complete and as per the directions of the Engineer-in-charge of the work	No.	650.00	Rupees Six Hundred Fifty Only
A	27	Carbon Housing etc., complete and as per the directions of the Engineer-in-charge of the work	No.	475.00	Rupees Four Hundred Seventy Five Only
B	27	Thrust bearing block assembly complete with Segment bearing pad etc., complete and as per the directions of the Engineer-in-charge of the work	No.	1150.00	Rupees One Thousand One Hundred Fifty Only
C	27	Oil Seal etc., complete and as per the directions of the Engineer-in-charge of the work	No.	125.00	Rupees One Hundred Twenty Five Only
D	27	Oil Seal Steel Bush etc., complete and as per the directions of the Engineer-in-charge of the work	No.	150.00	Rupees One Hundred Fifty Only
E	400	Guide vane etc., complete and as per the directions of the Engineer-in-charge of the work	No.	175.00	Rupees One Hundred Seventy Five Only
F	400	Impeller Shell moulded with aluminium Bronze) etc., complete and as per the directions of the Engineer-in-charge of the work	No.	425.00	Rupees Four Hundred Twenty Five Only
G	27	Discharge outlet (D.O) Bearing D.O Steel Bush etc., complete and as per the directions of the Engineer-in-charge of the work	No.	445.00	Rupees Four Hundred Forty Five Only
H	27	Steel Bush etc., complete and as per the directions of the Engineer-in-charge of the work	No.	150.00	Rupees One Hundred Fifty Only
I	27	Pump shaft made out of stainless steel Centreless ground with key way (upto 8 stages) etc., complete and as per the directions of the Engineer-in-charge of the work	No.	950.00	Rupees Nine Hundred Fifty Only

Signature of the contractor

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010

20/9

Executive Engineer

20/09

	Approved Quantity	Description	Unit	KRIDL Rates	
				In Figures	In Words
	27	Non – return valve (NRV) assembly complete with rubber 'O' Ring etc., complete and as per the directions of the Engineer-in-charge of the work	No.	1350.00	Rupees One Thousand Three Hundred Fifty Only
6	27	Cable Guard etc., complete and as per the directions of the Engineer-in-charge of the work	No.	150.00	Rupees One Hundred Fifty Only
37	27	Brass Filter etc., complete and as per the directions of the Engineer-in-charge of the work	No.	250.00	Rupees Two Hundred Fifty Only
38	27	Re-erection charges of pumping machineries including overhauling and pointing etc., complete and as per the directions of the Engineer-in-charge of the work	Each	950.00	Rupees Nine Hundred Fifty Only
39	520.00	Supplying and drawing 3 core flat PVC sheathed submersible pump cable manufactured with electrolytic grade copper with flexible copper with low resistance conductor confirming to table 3 class 5 of IS:8130-1984 and virgin grade PVC insulation and powder coating extruded PVC sheathed suitable for working voltage upto 1100Volts as per IS-694:1990 & confirming to GTP of **GROUP-A. 3C x 4 Sqm mm** etc., complete and as per the directions of the Engineer-in-charge of the work	Mtr	126.70	Rupees One Hundred Twenty Six And Paise Seventy Only
40		**C) Replacement of pump parts:** The following main components of submersible pump sets requiring replacement.			
41	1	Oil Seal	No.	125.00	Rupees One Hundred Twenty Five Only
42	1	Oil Seal Steel Bush	No.	150.00	Rupees One Hundred Fifty Only
43	15	Guide vane	No.	175.00	Rupees One Hundred Seventy Five Only
44	15	Impeller Shell moulded with aluminium Bronze)	No.	425.00	Rupees Four Hundred Twenty Five Only
45	1	Discharge outlet (D.O) Bearing D.O Steel Bush	No.	445.00	Rupees Four Hundred Forty Five Only
46	1	Steel Bush	No.	150.00	Rupees One Hundred Fifty Only
47	1	Pump shaft made out of stainless steel Centreless ground with key way (upto 8 stages)	No.	950.00	Rupees Nine Hundred Fifty Only
48	1	Non – return valve (NRV) assembly complete with rubber 'O' Ring	No.	1350.00	Rupees One Thousand Three Hundred Fifty Only
49	1	Cable Guard	No.	150.00	Rupees One Hundred Fifty Only
50	1	Brass Filter	No.	250.00	Rupees Two Hundred Fifty Only
51	1	Re-erection charges of pumping machineries including overhauling and pointing	Each	950.00	Rupees Nine Hundred Fifty Only
52	890	Supply of drinking waster through water tankers of capacity 3000 liters including hiring of water tnker, hiring of tractor 40 HP including cost of water and engaging heavy mazdoor to deliver water from source to supply point including cost of fuel, lubricants, men and machinery all leads and lifts transporation, labour etc complete	Trips	452.00	Rupees Four Hundred Fifty Two Only

Signature of the Contractor

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010

20/09

Executive Engineer
Byatarayanapura Division
BBMP, Bangalore.

20/09